[illegible]

CONTROLS ARE DESIGN/BUILD WITH DESIGN OF THE CONTROL SYSTEM DELEGATED TO THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A COMPLETELY FUNCTIONAL CONTROL SYSTEM THAT PERFORMS THE SERVICES BELOW. FURNISH ALL LABOR, MATERIALS, AND EQUIPMENT NECESSARY FOR A COMPLETE AND OPERATING BUILDING MANAGEMENT SYSTEM (BAS), UTILIZING DIRECT DIGITAL CONTROLS AS SHOWN ON THE DRAWINGS AND AS DESCRIBED HEREIN. ALL CONTROLLERS FURNISHED IN THIS SECTION SHALL COMMUNICATE ON A PEER-TO-PEER BUS OVER AN OPEN PROTOCOL BUS OR IP NETWORK THAT COMPLIES WITH ANSI/ASHRAE STANDARD 135 NATIVE BACNET DEVICES. CONTRACTOR TO PULL POWER REQUIRED FOR CONTROLS FROM SPARE BREAKERS IN THE LIGHTING PANEL.


CONTROLS SHALL BE INTEGRATED INTO THE EXISTING BUILDING AUTOMATION SYSTEM FRONT-END

- OWNER CONTROL SYSTEM TRAINING AND OWNER DESIRED SYSTEM REPROGRAMMING SHALL BE PROVIDED AT THE FOLLOWING INTERVALS:
 - AFTER AHU-1 INSTALLATION
 - 3 MONTHS AFTER ALL INSTALLATIONS HAVE BEEN COMPLETED
 - INCLUDE 20 HOURS OF REPROGRAMMING TIME DURING THE FIRST YEAR OF OCCUPANCY TO BE USED AT THE OWNER'S DISCRETION.
- PROVIDE ONE YEAR WARRANTY ON PARTS AND LABOR.
- PROVIDE CONTROL'S SUBMITTAL FOR REVIEW BY OWNER AND ENGINEER THAT INCLUDE THE FOLLOWING:
 - NETWORK COMMUNICATIONS DIAGRAM
 - FRONT END GRAPHICS
 - SEQUENCE OF OPERATIONS
 - POINTS LIST
 - SETPOINTS
- PROVIDE AS-BUILT CONTROL DRAWINGS
 - NETWORK COMMUNICATIONS DIAGRAM
 - FRONT END GRAPHICS
 - SEQUENCE OF OPERATIONS
 - POINTS LIST
 - SETPOINTS
 - POINT-TO-POINT COMMISSIONING REPORT
 - PERFORMANCE VERIFICATION SHEETS
 - CONTROLLER CHECKOUT/CALIBRATION SHEETS
- ANY CONTROL WIRING THAT WILL NOT BE CONCEALED SHALL BE INSTALLED IN CONDUIT
- COORDINATE CONTROL PANEL LOCATION(S) WITH OWNER
- CONTROLS SERVING UNIT SHALL BE ON AN UNINTERRUPTED POWER SUPPLY (UPS) WITH SURGE PROTECTION. LOCATE UPS WITHIN THE CONTROL PANEL.

- OCCUPIED HEATING SETPOINT = 70°F (ADJ)
- OCCUPIED COOLING SETPOINT = 74°F (ADJ)
- UNOCCUPIED HEATING SETPOINT = 66°F (ADJ)
- UNOCCUPIED COOLING SETPOINT = 78°F (ADJ)
- MAXIMUM RELATIVE HUMIDITY SETPOINT = 60% RH (ADJ)

- ADJUST THE OCCUPIED TEMPERATURE SETPOINT ANYWHERE IN THE RANGE OF 66°F-78°F (ADJ)
- ADJUST THE MAXIMUM RELATIVE HUMIDITY SETPOINT IN THE RANGE OF 50% MAX – 60% MAX
- OVERRIDE THE OCCUPANCY SCHEDULE FOR 2 HOURS (ADJ)
- DISPLAY SPACE TEMPERATURE
- DISPLAY RELATIVE HUMIDITY
- DISPLAY OCCUPIED/UNOCCUPIED STATUS

- .. RETURN AIR TEMPERATURE
- .. OUTDOOR AIR TEMPERATURE
- .. MIXED AIR TEMPERATURE
- .. RETURN AIR DAMPER COMMAND
- .. RETURN AIR DAMPER POSITION
- .. OUTSIDE AIR DAMPER COMMAND
- .. OUTSIDE AIR DAMPER POSITION
- .. PRESSURE DROP ACROSS AIR FILTER
- .. COOLING COIL CONTROL VALVE COMMAND
- .. COOLING COIL CONTROL VALVE POSITION
- .. HEATING COIL CONTROL VALVE COMMAND
- .. HEATING COIL CONTROL VALVE POSITION
- .. SUPPLY AIR TEMPERATURE
- .. SUPPLY FAN COMMAND
- .. SUPPLY FAN STATUS
- .. SPACE TEMPERATURE SETPOINT
- .. SPACE TEMPERATURE
- .. SPACE RELATIVE HUMIDITY SETPOINT
- .. SPACE RELATIVE HUMIDITY
- .. OCCUPIED/UNOCCUPIED COMMAND
- .. OCCUPIED/UNOCCUPIED STATUS
- SEQUENCE OF OPERATIONS:
 - .. OCCUPIED MODE: WHEN THE BUILDING IS OCCUPIED PER THE OCCUPANCY SCHEDULE OR A SCHEDULE OVERRIDE:
 - ... RUN SUPPLY FAN AT SPEED DETERMINED DURING BALANCING TO PROVIDE FULL DESIGN AIRFLOW. THE FAN SPEED TO ACHIEVE FULL AIRFLOW AS DETERMINED DURING BALANCING SHOULD BE NOTED ON THE CONTROL GRAPHIC AS AN UNEDITABLE NOTE AND THE PROGRAMMING SHALL NOT ALLOW THE FAN SPEED TO GO OVER THE FULL FLOW.
 - ... WHEN ECONOMIZING IS NOT AVAILABLE: MODULATE OUTDOOR AIR AND RETURN AIR DAMPER TO PROVIDE THE OUTSIDE AIRFLOW SHOWN IN THE AHU SCHEDULE. THE DAMPER POSITIONS TO ACHIEVE THE OUTSIDE AIRFLOW SHOWN ON THE SCHEDULE SHOULD BE NOTED ON THE CONTROL GRAPHICS AS AN UN-EDITABLE NOTE.
 - ... WHEN ECONOMIZING IS AVAILABLE: MODULATE OUTDOOR AIR AND RETURN AIR DAMPER TO PROVIDE 55°F DISCHARGE AIR (ADJ).
 - ... IF ZONE TEMPERATURE IS ABOVE THE COOLING TEMPERATURE SETPOINT, MODULATE THE COOLING COIL CONTROL VALVE TO MEET THE COOLING TEMPERATURE SETPOINT.
 - ... IF ZONE TEMPERATURE IS BELOW THE HEATING TEMPERATURE SETPOINT, MODULATE THE HEATING COIL CONTROL VALVE TO MEET THE HEATING TEMPERATURE SETPOINT.
 - ... IF ZONE RELATIVE HUMIDITY IS ABOVE MAXIMUM RELATIVE HUMIDITY SETPOINT, OPEN COOLING COIL CONTROL VALVE TO 100% AND MODULATE HEATING CONTROL VALVE TO MAINTAIN THE HEATING TEMPERATURE SETPOINT.
 - .. UNOCCUPIED MODE: WHEN THE BUILDING IS UNOCCUPIED PER THE OCCUPANCY SCHEDULE:
 - ... CLOSE OUTSIDE AIR DAMPER AND FULLY OPEN RETURN AIR DAMPER.
 - ... IF TEMPERATURE WITHIN ZONE IS WITHIN UNOCCUPIED SETPOINTS, TURN SUPPLY FAN OFF.
 - ... IF ZONE TEMPERATURE IS ABOVE THE COOLING TEMPERATURE SETPOINT, MODULATE THE COOLING COIL CONTROL VALVE TO MEET THE COOLING TEMPERATURE SETPOINT.
 - ... IF ZONE TEMPERATURE IS BELOW THE HEATING TEMPERATURE SETPOINT, MODULATE THE HEATING COIL CONTROL VALVE TO MEET THE HEATING TEMPERATURE SETPOINT.
 - ... IF ZONE RELATIVE HUMIDITY IS ABOVE MAXIMUM RELATIVE HUMIDITY SETPOINT, OPEN COOLING COIL CONTROL VALVE TO 100% AND MODULATE HEATING CONTROL VALVE TO MAINTAIN THE HEATING TEMPERATURE SETPOINT.



AHU-1 HVAC UPGRADES

200 N MIDWEST BLVD
MIDWEST CITY, OK 73110

CONTROL NOTES

INITIAL DATE: 02.04.26		JOB NO: 3147.01
OWN BY: HCS	CHECKED BY: AMM	SHEET: M-4
PRINT DATE: 2/4/2026		SHEET NO: 4 OF 4